

Caravan heating Installation manual

The package consist of the following parts:

- The heating foil 42 volt 100 W per m2 **inclusive the connection wires.**
- Transformer.

While installing the Mobile Home Floor heating System, please make allowance for the following points:

- The system is delivered complete and can be rolled out on the surface you want to heat..
- Make sure that when the system is rolled out, no layers are put on or over each other. This can course to much heat.
- When a layer is too long, you can cut the foil into the right measure. Cut the foil between the black layers and tape the ends with electrical tape. (Only do this while the plug is not connected to the electrical circuit).
- Do not cover the Heated surface with heavy part or equipment because this can course Heatspots

After installation please make allowance for the following points:

- The reaction time is about 15 minutes.
- The system may not be folded, cut in or be used while being wet.
- Always be careful for thermal blockage of the system. The heat of the heating system must be able to be released.
- If you clean the mat with water, please let it dry for at least 24 hours before using the system again.
- If you spill fluids (coffee, tea or lemonade) pull the plug out, remove the stains and let the mat dry before using it again.

We advise you to regulate the system on a time clock or with a thermostat.

We wish you a lot of enjoyable warmth with you floor heating system.

